



Republic of Serbia  
Municipality of Surdulica  
Kralja Petra I no.1  
Tel./fax. 0038117815270  
www.surdulica.org

12.03.2014

### FREQUENTLY ASKED QUESTIONS

**Project title:** WORKS TENDER PROCEDURE FOR RECONSTRUCTION AND REHABILITATION OF AN INFORMATION CENTER FOR ENVIRONMENT PROTECTION IN "VLASINA" PROTECTED AREA IN SURDULICA

**Publication Ref:** 2007CB16IPO006-2011-2-179 PP2/2 WORKS (404-3/14-01)

**Contracting Authority:** Municipality of Surdulica

QUESTION	ANSWER
A – Civil engineering works, ITEM XIV.1.a – wooden joinery and Technical Specification – page 26 – wooden doors. It is not specified what is the finish of the doors, veneer or painting. Also, please specify whether the door frames require mass or MDF.	The finish of the door is veneer. The door frames are the same as door leaf.
C – FURNISHING and Technical specification – pages 27-31 – the furniture made of laminated materials (tables, cabinets etc.). Please specify the thickness of material, and the finish (staining, varnish, finishing varnish...). Also, if it is possible, please provide us with the drawings of the furniture in order to give a good offer, because the descriptions do not provide enough information.	Thickness: For tables upper panel: 32mm; For cabinets and else: 19 mm The finish: varnishing with polyurethane varnish; staining in colour golden oak <b>Corrected through Corrigendum No.1.</b>  Interior design does not exist.

<p>C – FURNISHING, Item II/2 – the chairs - please provide us with a more detailed description, both, in terms of structure, and the cover.</p>	<p>1. Chairs for the conference room. Metal frame (high gloss chrome finish) cushioned seat and back from eko leather. Colour: black.</p> <p>2. Office chair. Fixed armrests. Back height and angle adjustment. High back. Seat height adjustment. Cushioned seat and back from eko leather. Smooth running casters, 360 degrees swivel. Colour: Black</p> <p>3. Chair for kitchen. Metal frame (high gloss chrome finish) cushioned seat and back (single colour fabric). Colour: brown.</p> <p><b>Corrected through Corrigendum No.1.</b></p>
<p>A – Civil engineering works ITEM V – Masonry works – article 5 and 6. Procurement, transport and plastering of walls from the inside on concrete and brick base, in two layers with compo mortar ratio 1:3:9 with all the necessary preliminary work by using auxiliary scaffolding. Total 1600,00m<sup>2</sup>. Are these articles doubled?</p>	<p>Position 6 in part A – Civil engineering works ITEM V – Masonry works is deleted in its entirety. Position 7 is now position 6 in Section B) Redevelopment and extension of the existing facility, table – V Masonry works. <b>Corrected through Corrigendum No.1.</b></p>

Novica Toncev,

Mayor of Municipality of Surdulica

